

PROFORMA P.W.G. EIRL
BRUHAT BENGALooru MAHANAGARA PALIKE


Name of Work: Providing & laying of sanitary pipe line 230mm dia glazed stone ware and 300mm dia RCC pipe line at Kurlappa layout near kogilu road (Ward No.1 Yelahanka

Estimate Cost :Rs.3250000.00

Agreement Cost : Rs 3115458.00


Tender Premium : 5.0 % above

Sl. No	Tender Item	Description	Unit	Anticipated Qty			Remarks
				Qty	Rate	Amount	
1		2	3	10	11	12	24
2	2	Supplying DOUBLE WALL CORRUGATED (External annul corrugated & smooth internal wall) (DWC) of class SN 8, piping system in accordance with IS 16098 (Part-2) and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading and unloading at both destinations and cuts of pipes wherever necessary including jointing with all labour, lead & lifts, including encasing the pipes alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (BWSSB SR 2017-18,P no 26, Code no 4295 & 4296)	Rmt	301	1384.95	416870	During the inspection of Honorable MLA & CE (Yelahanka Zone) considering the difficuty in execution of laying of pipe line , it was instructed to adopt the new techngolgy , I e RCC pipe line is changed to N P-8 Double wall corregated pipe , hence item is changed.
Rs Four lakhs Sixteen Thosand Eight hudred Seventy only						416870	


Assistant Engineer
Ward No.1


Assistant Executive Engineer
Yelahanka Sub Division


Executive Engineer
Yelahanka Division



ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯುಪವಿ ಪಾಲಿಕೆ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

BRUHAT BENGALooru MAHANAGARA PALIKE


YELAHANKA ZONE

Name of Work: Providing & laying of sanitary pipe line 230mm dia glazed stone ware and 300mm dia RCC pipe line at Kurlappa layout near kogilu road (Ward No.1 Yelahanka CMC area

EIRL No.1		RATE ANALYSIS	
1	Installation of steel product pipe by HDD method including preparing and setting up the plant and equipment, preparing new pipe work materials, installing new pipe work and commissioning system or making the system ready for commissioning by HDD operation including all related civil and mechanical works like excavation, shoring / strutting etc. drilling, stringing, ramming and pulling back the new work on the design bore path alignment, proper disposal of drilling fluid and restoration of site after completion etc, for horizontal directional drilling technique suiting Indian conditions in all types of soil including the cost of sleeve / casing pipe etc. in all respects for: 400 mm dia and 6 mm thick.	Unit	
	BWSSB SR 2017-18 , P.No.192, SLI.No 4.7 U030G	Rmt	13017
	Add tender premium 5%		650.9
	Say Rs Thirteen thousand & Six Hundred Sixty Seven and paise Eighty five only		13667.85


Assistant Engineer
Ward (No.1)


Assistant Executive Engineer
Yelahanka


Executive Engineer
Yelahanka Zone